

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

7/18/95 J.P.P.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

241

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T15N R2W	M-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

14 AUG 95 3:04 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on MAY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
M-5 East Section Corner 12 & 13, CORNER COMMON TO A-5, T15N-R1W
1830 CLARK, T15N, R2W, MAPLE 14" S43°E 52 LKS., HEMLOCK 12" N75°E 17 LKS., BURT FOUND OLD CORNER IN 1852.
1946 CONSUMERS POWER CO. ENG. OLD BOILER GRATE & HUNK OF IRON FOUND BY M.D. STITT
1972 WHITTIER 1"x1/2" STEEL BAR WITH WOOD POST - UNRECORDED SURVEY

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-5 East Section Corner 12 & 13
Found cabin spike over hunk of iron, meas. N 1311.98 per Whittier Survey to 1/2" rod in ditch (pipe 33' West) and South 2633.5 feet to A-6.

SURVEY &
REMONUMENTATION
NOV 1995
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner, M-5 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 19 95.

M-5 East Section Corner 12 & 13
Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box per surveys by C.P.Co. and Whittier. Accepted as best available evidence of the accepted position of the corner.

- S45°E 58.4' - FIRE HYD.
- S45°W 58.0' - N&T IN POWER POLE
- N40°W 47.7' - N&T IN 12" PINE
- N57°E 56.0' - N&T IN POWER POLE



Signed by Paul B. Lapham Date 7/21/95
Surveyor's Michigan License No. 9433