

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

342

8/10/97

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T15N R2W	M-7 ✓
	T15N R1W	A-7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED  
REMONUMENTATION  
11 DEC 97 11:59 A.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **MARK R. ROBISON**, in a field survey on **July 1**, 19 **97** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Clark  
Wil.-Pine 8 N29W 17  
Pine 26 S63W 6

8-18-73 Loukus, L.C.R.C. 238  
Set 3/4" Pipe S.P.M.  
Wil.-N43W 47.09 F. Post  
N75E 35.07 F. Post  
S52W 50.19 6" Elm

10-27-15 Gibbs  
Set Pine Root Post in  
place of old corner  
North 39.96 to M-6  
West 40.54 to L-7

SURVEY &  
REMONUMENTATION

FEB 24 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" capped pipe 12.00 ft. South and 0.4 ft. West of a large square-head bolt. Measured from bolt to North 2633.47 (C.S.R. 2637.36) to remon corner at M-6 and West 2671.00 (C.S.R. 2675.64) to C.I. at L-7 and South 5287.88 to M-9. Accepted bolt as position of corner because it fit C.S.R. records. Removed pipe. Corner is common to T15N, R1W.

Corners, M-7, T15N, R2W, & A-7, T15N, R1W, were approved for remonumentation at a Peer Review Committee Meeting on August 1, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of position of C.S.R. Corner.

Witnesses:

East 34.12', nail & tag, Fence Post  
N45W 45.92', nail & tag, Post (old utility pole)  
N36E 74.54', nail & tag, 13" Red Oak  
N72W 90.80', nail & tag, 8" Red Pine

Signed by

*Mark R. Robison*

Date 10-31-97

Surveyor's Michigan License No.

27458

