

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**APPROVED LAND CORNER**  
**P.A. 345 OF 1990**  
**MIDLAND COUNTY**

*4/28/94 JLG*

For corners in

<u>MIDLAND</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T <u>15N</u> R <u>1E</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**178**

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

21 DEC 94 11:16 A.M.

Register of Deeds Stamp & File Number

BEVERLY J THAYER

REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1831 HARVEY PARKE  
INT. MER. 7.90 CH. N OF SEC. COR.  
WIT.-(1)B. ASH 8" N11°E, 40 LKS.  
(2)ASPEN 5" S19°E 26 LKS.

NO C.S.R.

8-21-67 M.S.H.D. RIGHT-OF-WAY MAPS.

3-4-87 PAUL LAPHAM, L.C.R.C. #638  
& (132) L.4, PG.17  
FOUND MON. BOX  
WIT.-(3)N50°E 62.15' TELE. POLE  
(4)N60°W 76.80' TELE. POLE  
(5)N70°W 75.80' TELE. RISER  
(6)EAST 2.3' M-30

6-30-92 MARK ROBISON  
FOUND MON. BOX  
WIT.-(3), (4), (5) & (6) ABOVE

4-1-92 JERRY JONES  
FOUND BRASS CAP IN MON. BOX  
WIT.(4) & (6) ABOVE  
(7)S50°W N&T IN POWER POLE 57.26'  
(8)N50°E N&T IN GUY POLE 60.20'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND M.S.H.D. CAPPED IRON 2" DEEP IN MON. BOX. COULD NOT REMOVE.  
FOUND WITNESSES 4, 5, 6, 7 & 8.  
MEASURED SOUTH 521.44' TO M-3 T15N, R1W (G.L.O. 521.40')

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, E-5 was approved for remonumentation at a Peer Review Committee Meeting on Nov. 28, 1994.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**E-5: Corner common to Sections 9 & 16**  
ACCEPTED M.S.H.D. BRASS CAP & IRON IN MON. BOX AS SUBSTITUTE FOR STANDARD MIDLAND COUNTY MONUMENT.  
WITNESSES:  
N60°W 76.80' N&T IN TELE. POLE (4)  
N70°W 75.80' CENTER OF TEL. RISER (5)  
S50°W 57.26' N&T IN POWER POLE (7)  
N50°E 60.20' N&T IN GUY POLE(8)



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 12-19-94