

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

248

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in 7/18/95 929

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

14 AUG 95 3:05 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>1E</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 WEST 1/4 CORNER SECTION 21
1831 HARVEY PARK, NOT SET IN GOV'T SURVEY
1918 GIBBS, SET GAS PIPE FOR CORNER AT AVERAGE DISTANCE ON TRUE LINE. 7.145 CH (NOTED 471.90 FEET)
NORTH OF E 1/4 COR. SEC. 13, T15N, R1W
HIGHWAY SURVEYS DID NOT ESTABLISH CORNER
AYRES FILES, CORNER FALLS 7.145 CH (471.57') NORTH OF E 1/4 CORNER SEC. 13, T15N, R1W
12-13-57 HUNTER, CORNER FALLS 471.90 FEET NORTH OF E 1/4 CORNER SEC. 13, T15N, R1W, SURVEY
2-20-69 WHITTIER, SAME AS ABOVE, SURVEY
5-14-69 WHITTIER, SAME AS ABOVE, SURVEY

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 WEST 1/4 CORNER SECTION 21

Did not find corner. Set 5/8" x 36" iron 471.90 feet North of E 1/4 Cor. Section 13 T15N, R1W in line with N.E. Corner of Section 13 per surveys & file records. Measured South 2643.42 feet to E-9 (C.S.R. - 2653.2). Hunter survey shows 2654.96 North to E-7.

SURVEY &
REMONUMENTATION

NOV 1995

COMMISSION

Corner, E-8 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 19 95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 WEST 1/4 CORNER SECTION 21
Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box per surveys by Gibbs, Hunter, Whittier. Accepted as best evidence of the accepted position of the corner.

Signed by Paul B. Lapham

Date 9/21/95

Surveyor's Michigan License No. 9433

