

APPROVED LAND CORNER

451

P.A. 345 OF 1990
MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Midland County Remonumentation

4/23/99 JLR

For Corners in
Midland
(County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>15N</u> R. <u>1E</u>	<u>K-8</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED
12/7/1999 2:59:31 PM
SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Parke
40. 1/4 Sec Post
Maple 10 N63W 7
W. Oak 9 S78E 22

1979 Schafer, (132) 2-857
Fd 1/2" Pipe
S50E 56.18 N & T in P.P.
N45E 46.41 N & T in S.E/S Tw 12" Oak
S45W 70.30 N & D in P.P.

1982 Beryl Jones LCRC #640
Fd Iron
S60W 70.20 P.P.
S55E 36.60 P.P.
East 33.10 Conc. Mon

1992 J. Jones, (132) 4-873
Fd 1/2" Pipe
East 33.05 Mon
S45E 36.42 N & D in P.P.
S44W 54.33 C.L. Fire Hyd't
S48W 70.35 N & D in P.P.
2' N of C.L. Rd to West

SURVEY &
REMONUMENTATION
FEB 09 2000
SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Found 1/2" Pipe in Mon. Box. Found two 1979 witnesses, three 1982 witnesses and five 1992 witnesses. Measured North 2646.10, turned 180° 00' 15" R and measured South 2658.08 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 18" Midland Co. Remon marked P.S. #27458 in existing Mon. Box. Accepted as best available evidence of the original position of the corner.

Witnesses:
N57°E 46.58 N & T in 14" x 14" Tw. Oak (OBT)
S56°E, 36.44 N & T in P.P. (OBT)
S50°W, 70.38 N & T in P.P. (OBT)
N15°W, 113.04 N & T in 14" x 8" x 7" Tr. Oak

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 11-29-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983