

APPROVED LAND CORNER

P.A. 345 OF 1990
MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Midland County Remonumentation

4/23/99

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

For Corners in
Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 15N R. 1E K-9
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 Parke
80. Post to Cor 23, 24, 25, & 26
Tamrk 5 S87E 18
do 6 S71W 10

1978 Schafer, (132) 2-555
Fd R.R. spike in pvm't

1978 Schafer, (132) 2-628
Fd R.R. spike in pvm't

1982 Jones LCRC #640
Fd R.R. spike
S60W 75.70 P.P.
N45E 54.35 S. Post in gate
East 5.70 Road C.L.

1992 Jones, (132) 4-873
Fd R.R. spike
S45W 75.76 N & D in P.P.
N45W 30.55 N. Rivet W. end CMP
N50E 34.20 N. Rivet E. end CMP
N30E 54.34 N & D in gate post

1995 Jones, (132) 5-267
Fd R.R. spike
S50W 75.80 N & D in P.P.
S30W 45.37 C.L. Fire Hyd't
N30E 54.14 N & D in gate post
N45W 30.53 N. Rivet in W. end CMP

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found 3/4" pipe in Mon. Box 6.6 feet W and 2 feet S of int C.L. Found two 1978 witnesses, two 1982 witnesses, four 1992 witnesses and four 1995 witnesses. Meas. N 2658.08 feet and South 2661.30 feet. Accepted existing pipe as corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Brass Cap stamped "Midland County Remon Cor. P.S. #27458" on existing 3/4" pipe in Mon. Box. Accepted as best available evidence of original position of the corner.

- Witnesses:
- N45°E, 54.12 N & T in P.P. Gate Post (OBT)
 - S39°W, 45.40 C.L. Fire Hyd't (OBT)
 - S56°W, 75.86 N & T in P.P. (OBT)
 - N33°W, 30.56 North rivet in W. End 66" CMP (OBT)
 - S75°E, 34.18 North rivet in E. End 66" CMP (OBT)

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 11-29-99



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971