

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Midland County Remonumentation

453

11/23/99 *JLR*

For Corners in
Midland

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|-------------|
| 1. Public Land Survey | T. <u>15N</u> R. <u>1E</u> | <u>K-10</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 Parke
40. 1/4 Sec Post
Pine 26 N46E 46
Tamrk 11 S65W 55

1974 Schafer, (132) 2-188
Set S1/8 Cor on W line Sec. 25
1332.19 feet North of K-11

1978 Schafer, (132) 2-555
Found conc. nail in pvm't at N1/8
Cor on E line of Sec. 26,
1330.88 feet South of K-9

1989 Jones, (132) 4-415
References corner - No Witnesses

1995 Jones, (132) 5-267
Fd 1" pipe in Mon. Box
S53W 64.45 C.L. Fire Hyd't
S58E 44.38 C.L. Conc. Project Marker
N45E 74.25 N & D in P.P.
N25W 54.10 C.L. Top. Water Valve

**SURVEY &
REMONUMENTATION**

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" x 18" pipe in Mon. Box 1/2 foot W and 4 1/2 feet S of int. C.L. Found two 1995 witnesses. Meas. North 2661.30 feet, measured 179° 55' 20" R. and measured S 2664.08 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 18" Gas Pipe with Clare Co. Remon Cap marked P.S. #27458 in existing Mon. Box. Accepted as best available evidence of the original position of the corner.

Witnesses:

N46°E, 141.98 N & T in P.P.
S10°E, 127.50 N & T in 10 x 10 x 8 Ash
S64°W, 64.46 Top. Cen Fire Hyd't (OBT)
N49°W, 78.92 N & T in P.P.
S45°E, 44.46 Top. Cen. Proj. Marker (OBT)

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458



Date 11-29-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971