

SURVEY &
REMONUMENTATION

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

APR 28 1995

COMMISSION

97

9/21/94 *[Signature]*

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MIDLAND (County)	Located In:	Corner Code #
Public Land Survey	T 15N R 1E	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
FILED 2-REMON

28 SEP 94 3:32 P.M.

Register of Deeds Stamp & File Number
BEVERLY J THAYER

REGISTER OF DEEDS

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PAUL B. LAPHAM, in a field survey on JUNE, 19 94

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- L-13: South 1/4 Corner, Section 36
- 1831 - Parke Set 1/2 Mile Post, Hemlock 13" N 74°E 14 lks, Hemlock 16" N 84°W 33 lks
- 11/27/01 - Gibbs, Old Corner Post w/ Crockery around C.S.R. 1-22
- 01/18/73 - David B. Whittier, No reference to corner but establishes N-S 1/4 line direction. (132) L1, P275

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13: South 1/4 Corner, Section 36
- Established position of Corner by extending Survey recorded Liber 1, page 275 by Dave Whittier and Found a 12" Boat Spike in Monument Box, 2652.57' South of Center of Section; Excavated to 3 feet and found broken crockery per Gibbs C.S.R. 1-22.

Accepted as best available evidence of the perpetuation of the original corner & replaced with Standard Monument.

South 1/4 Corner, L-13 was approved for remonumentation at a Peer Review Committee Meeting on SEP 21, 1994

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13: South 1/4 Corner, Section 36
- Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Mon. Box.
- N 38°E, 52.42' - Nail & Tag in Power Pole
- S 62°E, 101.65' - Nail & Tag in Power Pole
- SOUTH, 33.33' - Nail & Tag in Power Pole
- N 37°W, 65.10' - Nail & Tag in Power Pole
- EAST, 3.25' - R.R. Spike



signed by *Paul B. Lapham*
Surveyor's Michigan License No. 9433

Date 9-22-94