

SURVEY & REMONUMENTATION

APPROVED LAND CORNER P.A. 345 OF 1990 MIDLAND COUNTY

JAN 21 1999

REMON. COR. C-9, LARKIN TWP. LAND CORNER RECORDATION CERTIFICATE SECTION Filing Requirement of Act 74, Mich. P.A. 1970

406

For corners in Midland

Form with columns: (County), Located in:, Corner Code #. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

STATE OF MICHIGAN MIDLAND COUNTY REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on APRIL 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

C-9 Corner common to Sections 19, 20, 29, and 30. Glo survey, 1830's, set post. Survey by M. Hunter, 1963, 1969, Tamarack Acres No. 1, set monument. Survey by J. Jones, 1980, 1985, 1992, found 1/2" rod in mon box.



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Corner common to Sections 19, 20, 29, and 30. Found Ledy's rod and cap on top of concrete mon in mon box per surveys by M. Hunter and J. Jones.

Corner C-9 was approved for remonumentation at a Peer Review Committee Meeting on August 17, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Corner common to Sections 19, 20, 29, and 30. Found Ledy's rod and cap on top of concrete mon in mon box per surveys by M. Hunter and J. Jones, replaced rod with brass disc stamped Midland Co. Remon Cor. PS 29241, and is accepted as the best available evidence of the position of the accepted corner. S 45 Deg E, 61.15', nail in 20" Oak. N 45 Deg E, 68.03', nail and plug in 10" Maple. N 35 Deg W, 74.18', nail and tag in 8" Maple. N 80 Deg W, 53.34', nail and plastic disc in 10" Oak. S 45 Deg E, 61.11', nail and plastic disc in 20" Oak. Corner is on Centerline of both roads.

Signed by Rodney A. Claypool Date 09-11-98

Surveyor's Michigan License No. 29241