

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Midland County Remonumentation

11/23/99 JLR

For Corners in
Midland
(County)

Located In: Corner Code#:

- 1. Public Land Survey T. 15N R. 2E E-1
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831 Parke
77.86 Int. N. Bdy 1.05 W
Pine 34 S06E 9
Birch 12 S62W27
1980 J. Jones, (132) 3-116
Fd 2" Pipe
- 1915 Gibbs
Post for Cor
1983 Lapham LCRC #576
Fd 2" Pipe
N45W 52.65 10" Birch
N30E 59.65 P.P.
S05W 35.00 Guard Post
- 1976 Schafer, (132) 2-95
Fd 2" Pipe
Meas. S. 5134.3 feet to E-3

SURVEY &
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 2" x 36" Drive-shaft (spline end down). Found two 1983 witnesses. Meas. East 69.32' to Standard corner E-13. Meas. South 2497.60 to E-2 (GLO 2498.76).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland County Remon Cor. P.S. #27458 in Mon. Box. Accepted as best available evidence of the original position of the corner.

- Witnesses:
- S55°W, 64.94 N & T in 3" x 5" Brace Pole for cable riser.
 - N30°E, 59.60 N & T in P.P. (OBT)
 - N50°W, 117.54 N & T in 20" W. Pine
 - S43°E, 115.50 N & T in 12" W. Pine

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458



Date 11-29-99