

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Midland County Remonumentation

11/23/99 JRP

For Corners in
Midland
(County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>15N</u> R. <u>2E</u>	<u>E-2</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED
12/7/1999 2:59:31 PM
SCOTT I. HAINES
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Parke 40.00 1/4 Cor Pine 30 North 11 Pine 30 S8E 21	1915 Gibbs Stone old corner in ground Set 3 stones on top	1985 J. Jones (132) 3-759 References Corner Meas. North 1318.65 to 1/8 Cor
---	---	--

SURVEY & REMONUMENTATION
FEB 09 2000
SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 24" pipe in asphalt (2 layers, i.e. paved over pavement). Measured North 2497.60 to E-1 (GLO, 2498.76). Meas. South 2637.16 (GLO 2640) to E-3. E-2 is on line between E-1 & E-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland County Remon Cor. P.S. #27458" in Mon. Box. Accepted as best available evidence of the original position of the corner.

Witnesses:
N64°E, 33.50 N & T in P.P.
S75°W, 44.60 N & T in P.P.
S31°W, 66.62 N & T in 15" Ash
S11°E, 184.74 N & T in P.P.

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 11-29-99