

**SURVEY &
REMONUMENTATION**

**APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY**

OCT 0 3 1996

**REMON. COR. E-13, LARKIN TWP.
LAND CORNER RECORDATION CERTIFICATE COMMISSION 264
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

22 AUG 96 8:05 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

For corners in
Midland
(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|------------|------|
| 1. Public Land Survey | T 15N R 2E | E-13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S T R | |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RODNEY CLAYPOOL, in a field survey on MAY 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-13 Section corner common to Sections 32 and 33 on south townline
- Survey by Government, 1830's
 - Survey by F. Gibbs, 1915, found 1/2" bar
 - Survey by M. Hunter, 1944, 1948, 1953, 1962
 - Survey by MDOT, 1958
 - Survey by J. Jones, 1984, 1990
 - Survey by R. Claypool, 1993



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13 Section corner common to Sections 32 and 33 on south townline
- Found bolt spike in mon box per surveys by M. Hunter, J. Jones, R. Claypool and LCRC by J. Erickson.

Corner E-13 was approved for remonumentation at a Peer Review Committee Meeting on 4/18/96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13 Section corner common to Sections 32 and 33 on south townline
- Found bolt spike in mon box, replaced bolt spike with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241 per surveys by M. Hunter, J. Jones, R. Claypool, and LCRC by J. Erickson; and is accepted as the best available evidence of the position of the accepted corner.

- N 54 Deg E, 65.56', SW cor brick planter
- S 50 Deg E, 68.63', NW bolt on Shell sign base
- N 52 Deg W, 58.25', nail in power pole
- S 56 Deg W, 63.06', centerline top R/W marker
- W, 11.80' to, E-1, T14N-R2E

Signed by Rodney D. Claypool Date 05-10-96

Surveyor's Michigan License No. 29241