

JAN 21 1999

APPROVED LAND CORNER P.A. 345 OF 1990 MIDLAND COUNTY

REMON. COR. F-3, LARKIN TWP. SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

405

8/17/98 [Signature]

For corners in Midland (County)

Table with columns: Located in: Corner Code #. Row 1: T 15N R 2E F-3

STATE OF MICHIGAN MIDLAND COUNTY REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat
5. Private Claims

I, RODNEY CLAYPOOL, in a field survey on APRIL 16, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and a central marker.

A. Description of original monument and accessories and/or subsequent restoration:

- F-3 1/4 corner common to Sections 4 and 9
Government survey, 1830's, set post
Survey by F. Gibbs, 1915, set old boiler flue
Dow Chemical Co. survey, 1950's?, boiler flue
Survey by M. MacDonald, 1984, (found)
Survey by J. Jones, 1989, 1995, 1996, found old boiler flue



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-3 1/4 corner common to Sections 4 and 9
Found 1 1/4" pipe (old boiler flue) per surveys by F. Gibbs, Dow Chemical Co., M. MacDonald, and J. Jones

Corner F-3 was approved for remonumentation at a Peer Review Committee Meeting on August 17, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-3 1/4 corner common to Sections 4 and 9
Found 1 1/4" pipe (old boiler flue) per surveys by F. Gibbs, Dow Chemical Co., M. MacDonald, and J. Jones, replaced pipe with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241 in mon box, and is accepted as the best available evidence of the position of the accepted corner.
N 20 Deg E, 109.30', nail in power pole
N 2 Deg E, 105.09', pk nail in power pole
N 40 Deg W, 45.42', nail and plastic disc in 8" Elm
S 2 Deg E, 33.14', pk nail in power pole
S 50 Deg E, 42.3', centerline C.B.

Signed by Rodney D. Claypool Date 09-11-98

Surveyor's Michigan License No. 29241