

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY**

**REMON. COR. G-4, LARKIN TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**145**

For corners in Midland  
(County)

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

28 NOV 94 1:00 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	Located in:	Corner Code #
	T 15N R 2E	G-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, RODNEY CLAYPOOL, in a field survey on FEB 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	1						
5												
6	18	17	16	15	14	1						
7												
8	19	20	21	22	23	2						
9												
10	30	29	28	27	26	2						
11												
12	31	32	33	34	35	3						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

G-4 Corner common to Sections 9 and 10

Government survey 1830's, set post Survey by F. Gibbs, 1917 set piece of wagon tire, stone around Survey by Dow, 1950's, 3/4" pipe Survey by M. Hunter, 1953, 1958, 1960 found stone and iron	Survey by D. Whittier, found corner Survey by J. Schafer 1974, 1976, 1977 found 3/4" pipe stones around Survey by J. Jones 1981, 1984, 1988, found corner LCRC by P. Lapham, 1983, found 3/8" rebar
--	---

**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-4 Corner common to Sections 9 and 10

Found 3/4" pipe (replaced with 5/8" rod and brass cap) per surveys by Dow, M. Hunter, D. Whittier, J. Schafer, J. Jones and LCRC by P. Lapham.

Corner G-4 was approved for remonumentation at a Peer Review Committee Meeting on Nov. 21, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-4 Corner common to Sections 9 and 10


Found 3/4" pipe (replaced pipe with 5/8" rod and brass cap stamped Midland County Remon. Cor. PS 29241, in mon box) per surveys by Dow, M. Hunter, D. Whittier, J. Schafer, J. Jones and LCRC by P. Lapham; and is accepted as the best available evidence of the accepted position of the corner.

S 45 Deg E, 54.00', PK nail in power pole S 50 Deg E, 52.24', nail in power pole	N 45 Deg W, 70.93', nail in 24" Oak S 45 Deg W, 54.67', PK nail in telephone pole
---	--

Signed by Rodney D. Claypool Date 11-28-94

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, 2924B, 1971



Revised May 4, 1981  
Revised Jan., 1982