

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY**

REMON. COR. I-8, LARKIN TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

147

11/21/94 *[Signature]*
For corners in
Midland
(County)

- | | | |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | Located in: | Corner Code # |
| | T <u>15N</u> R <u>2E</u> | <u>I-8</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
In Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

28 NOV 94 1:01 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on , 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	1						
5												
6	18	17	16	15	14	1						
7												
8	19	20	21	22	23	2						
9												
10	30	29	28	27	26	2						
11												
12	31	32	33	34	35	3						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-8 Corner common to Sections 22 and 23
- | | |
|--|--|
| Government survey 1830's, set wood post
Survey by F. Gibbs, 1907, 1911,
set ash post in place of old post
Survey by Dow, 1951, 3/4" pipe
Survey by M. Hunter, 1958, found corner | Survey by D. Whittier, 1967,
Waskevich Estates Subdivision
Survey by J. Schafer, 1971, found corner
Survey by D. Whittier, 1976, found mon
Survey by J. Schafer, 1979, found mon |
|--|--|

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-8 Corner common to Sections 22 and 23
- Found concrete mon (set 3/4" pipe and brass cap on top) per surveys by Dow, M. Hunter, D. Whittier, and J. Schafer.

Corner I-8 was approved for remonumentation at a Peer Review Committee Meeting on Nov 21, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-8 Corner common to Sections 22 and 23
- Found concrete mon (set 3/4" pipe and brass cap stamped Midland County Remon. Cor. PS 29241 in mon box) per surveys by Dow, M. Hunter, Whittier, and J. Schafer; and is accepted as the best available evidence of the accepted position of the corner.
- | | |
|---|---|
| S 45 Deg W, 66.03', nail and plastic disc in Maple clump
West, 32.91', concrete plat mon | North, 94.94', concrete plat mon
N 85 Deg W, 53.05', nail and plastic disc in 10" Pine |
|---|---|

Signed by Rodney D Claypool Date 11-28-94
Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, 1977
Revised May 14, 1977
Revised Jan, 1982

