

SURVEY &  
REMONUMENTATION

NOV 07 1994

COMMISSION

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

PS 29241/94

62

REMON. COR. L-1, LARKIN TOWNSHIP  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Midland

(County)

Located in: Corner Code #

- |                                       |                            |            |
|---------------------------------------|----------------------------|------------|
| 1. Public Land Survey                 | T <u>15</u> N R <u>2</u> E | <u>L-1</u> |
|                                       | T ___ R ___                | _____      |
|                                       | T ___ R ___                | _____      |
|                                       | T ___ R ___                | _____      |
| 2. Property Controlling<br>In Section | S ___ T ___ R ___          | _____      |
|                                       | S ___ T ___ R ___          | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___          | _____      |
|                                       | S ___ T ___ R ___          | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                            |            |
| 5. Private Claims _____               |                            |            |

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED

24 FEB 94 3:16 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on DECEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner common to Section 1

Not set in Original Government Survey

Survey by J. Jones 1993  
Found 1/2" rod

Survey by J. Schafer 1974  
Used corner

Survey by D. Ledy 1984  
Found 3/4" pipe  
N 20 Deg E, 40.91' to nail in power pole  
S 40 Deg E, 49.20' to nail in 14" Oak  
S 45 Deg W, 74.56' to nail in 20" Maple



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 1/4 corner common to Section 1

Found 1/2" rod in 3/4" pipe (set 3/4" pipe and brass cap in monument box) per surveys by J. Schafer, D. Ledy and J. Jones

Corner L-1 was approved for remonumentation at a Peer Review Committee Meeting on FEB 10, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Corner common to Section 1

Found 1/2" rod in 3/4" pipe (set 3/4" pipe and brass cap stamped "Midland Co. Remon. Cor. PS 29241" in monument box) per surveys by J. Schafer, D. Ledy and J. Jones and is accepted as the best perpetuation of the accepted position of the corner.

S 60 Deg E, 80.90' nail and plastic disc in Twin 12" Oak  
N 50 Deg E, 40.88' nail and plastic disc in power pole  
S 60 Deg W, 74.04' nail and plastic disc in 24" Maple Clump  
S 30 Deg W, 109.34' nail and plastic disc in 30" Oak

Signed by Rodney D. Claypool

Date 02-23-94

Surveyor's Michigan License No. 29241