

11/23/99 *[Signature]*

For Corners in
Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 15N R. 2E M-10
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 Parke
40.00 1/4 Cor
Sugar 9" for Corner

1996 Ledy
Fd 3/4" Pipe
SE 23.08 S. End 48" CMP
NE 33.10 N. End 48" CMP
SW 33.55 E. End 30" CMP
NW 46.45 Nail in N/S P.P.
NOTE: These Witnesses are good if we rotate them 90° left, i.e Ledy said North was to the East

SURVEY &
REMONUMENTATION

FEB 25 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 8" pipe over 3/4" x 18" pipe in Mon. Box. Found all 1996 witnesses rotated 90° to right, i.e. we must rotate them 90° left to fit. Meas. North 2643.11 to M-9. Meas. South 2641.52 to M-11. A-11, T15N, R3E is meas. 49.5 and recorded 49.56 feet (GLO 46.2) South of M-11 per McVean LCRC 03-91 Bay County Remon.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in existing Mon. Box. Accepted as best available evidence of the original position of the corner.

Witnesses:
N59°E, 46.46 N & T in P.P. (OBT)
S06°E, 249.16 N & T in P.P.
N78°W, 40.76 N & T in P.P.
N42°W, 140.04 N.E. Cor Brick Hse

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 11-29-99

