

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

SURVEY &
REMONUMENTATION

OCT 03 1996

REMON. COR. M-13, LARKIN TWP.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION 237

4/13/96 gsc

For corners in
Midland
(County)

1. Public Land Survey

Located in: Corner Code #

T 15N R 2E M-13 ✓
T R
T R
T R
S T R
S T R
S T R
S T R

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

22 AUG 96 8:06 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on JUNE 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Corner common to four Townships T14 & 15N-R2E and T14 & 15N-R3E

- Survey by Government (H. Parke), 1831, set post
- Survey by F. Gibbs, 1924
- Survey by Hunter, 1962
- H-W witness card, 1972
- Survey by J. Jones, 1981
- LCRC by C. McVean, 1994, (Bay Co. Remon Cor)



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Corner common to four Townships T14 & 15N-R2E and T14 & 15N-R3E

- Verified by witness card of 1972 (H-W Eng.)
- Found iron and brass cap in mon box (Bay Co. Remon Cor.), per surveys by M. Hunter, J. Jones, and LCRC by C. McVean.

Corner M-13 was approved for remonumentation at a Peer Review Committee Meeting on 4/13/96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Corner common to four Townships T14 & 15N-R2E and T14 & 15N-R3E

Found iron and brass cap in mon box (Bay Co. Remon Cor.), per surveys by M. Hunter, J. Jones, and LCRC by C. McVean; and is accepted as the best available evidence of the position of the accepted corner.

- S 45 Deg W, 42.07', nail and Bay Co. disc in power pole
- N 45 Deg W, 89.42', nail and Bay Co. disc in power pole
- N 40 Deg E, 79.80', nail and Bay Co. disc in power pole
- S 30 Deg E, 137.85', nail and Bay Co. disc in power pole

Signed by Rodney D. Claypool

Date 05-10-96

Surveyor's Michigan License No. 29241