

SURVEY & REMONUMENTATION

JAN 21 1999

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

367

For corners in

MIDLAND
(County)

Located in:

Corner Code #

1. Public Land Survey

T16N R01E

E-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
FILED
Remonumentation
12/16/1998 12:10:58 PM
BEVERLY J. THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

E-3: 1830 Parke
Int Mer 6.63 N of Cor
Wit-1)Beech 11 for Cor Tree

1-24-82 Jones (132) 3-389 Fd 3/4" Rod
Wit-none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3: Found 3/4" x 18" Iron. Measured South 656.68 feet to P.K. nail at NW Corner of Jones survey, (Liber 3, Page 389). Corner is 4.5 feet South of centerline road to East and on centerline of Meridian Road South. Measured East 2333.0 feet (GLO 2325.84) to 1/4 Corner.

Corner, E-3, was approved for remonumentation at a Peer Review Committee Meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-3: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
S80W 21.54', nail & tag, 23" Twin Maple
N28W 42.90', nail & tag, P.P.
N57E 109.34', nail & tag, 28" W. Pine
North 61.68', nail & tag, East side of 14" Twin W. Pine



Signed by Mark R. Robison

Surveyor's Michigan License No. 27458

Date 12-09-98

