

JAN 21 1999

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

373

9/09/98 *[Signature]*  
For corners in

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R01E	E-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

E-5: 1830 Parke 75.16, Int Mer 6.85 N of Cor  
of Secs 1 & 12, T16N R1W  
Wit-1) Ironwood 7" N60E 8 lks  
2) Ironwood 5" S42E 2 lks

1960 MDOT Project 56031R Book 5 of 6  
Found Axel Shaft 460.90 N of Std. Corner  
Wit-1) N15W 76.93 23" Elm  
2) N20E 82.40 8" Elm  
3) S70E 98.18 T. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5: Found 3/4" x 10" pipe over 1 1/2" x 36" axle shaft. Measured South 461.06 (GLO 452.1, MDOT 460.90) to Standard Corner Sections 1 and 12, T16N, R1W. Measured East 2320.54 (GLO 2320.56) to 1/4 Corner.

Corner, E-5, was approved for remonumentation at a Peer Review Committee Meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
S38E 68.76', nail & tag, P.P.  
South 292.28', nail & tag, P.P.  
N82E 303.14', nail & tag, P.P.  
West 25.91' South Leg of Street Sign



Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458

Date 12-09-98