

JAN 21 1999

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

368

For corners in 9/09/98 989

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R01E	F-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MIDLAND COUNTY
~~RECORDED~~
Remonumentation + Filed
12/16/1998 12:10:58 PM
BEVERLY J. THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- F-3: 1830 Parke Set 1/4 Post
Wit-1) Hemlock 9" N23W 19 lks
2) Hemlock 10" S30E 13 lks
- 3-20-73 Edmands Eng. (132) 1-348
Ref 1/4 Corner/Wit-none
- 7-8-81 Jones (132) 3-230 Fd 3/8" Rod
Wit-1) S5W 39.82 N&T in 10" Aspen
2) S35W 47.64 N&T in 9" Aspen
On centerline road E & W
Meas 2599.68 East to G-3
- 6-17-86 Jones (132) 3-885 Ref N 1/4 Cor
Meas East 1299.84 to 1/8 Cor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: Found 3/8" x 18" Iron over 5/8" x 30" Iron. Found 1981 witnesses. Measured West 2333.0 feet (GLO 2325.84) to Section Corner. Measured East 2599.72 (Jones 2599.68) feet to Section Corner.

Corner, F-3, was approved for remonumentation at a Peer Review Committee Meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
S05W 39.82', nail & tag, 12" Poplar (OBT)
S45W 51.32', nail & tag, 13" Poplar
North 72.56', nail & tag, 8" Ash
N20W 72.60', nail & tag, 7" Ash



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-09-98