

SURVEY & REMONUMENTATION

JAN 21 1999

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION 369

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

9/09/98 JLR

STATE OF MICHIGAN  
MIDLAND COUNTY

RECORDED  
Remonumentation & Filed  
12/16/1998 12:10:58 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

MIDLAND  
(County)

Located in:

Corner Code #

1. Public Land Survey	T	T16N R01E	G-3
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
6	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-3: 1830 Parke Set Cor Secs 3, 4, 9, & 10
  - Wit-1) Birch 14" S58W 15 lks
  - 2) Birch 9" N88E 14 lks
- 7-8-81 Jones (132) 3-230 Fd 5/8" Rod
  - Wit-1) S60W 64.69 N&T in P.P.
  - 2) N45W 85.51 N&T in P.P.
  - 5' E of centerline - Road to South
  - Meas 2599.68 W to F-3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3: Found 5/8" x 20" Iron over 1" x 1" x 16" Iron and 1/2" x 2" x 16" Iron Bar. Found all 1981 witnesses and checked 1981 distance from G-3 to F-3 at 2599.72 feet.

Corner, G-3, was approved for remonumentation at a Peer Review Committee meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- S64W 64.69', nail & tag, P.P. (OBT)
  - N41W 85.51', nail & tag, P.P. (OBT)
  - N45E 54.78', nail & tag, 4" x 6" Brace for Cable Riser
  - S24W 180.62', nail & tag, P.P.



Signed by Mark R. Robison

Date 12-09-98

Surveyor's Michigan License No. 27458