

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

289

9/12/96 JLP

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>1E</u>	<u>G-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

27 NOV 96 2:55 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1832 PARKE  
SET POST  
WIT.-BIRCH 11" S26°W 7 LKS.  
ELM 9" N30°E 22 LKS.

5-03-04 GIBBS, C.S.R.  
CEDAR POST OLD CORNER

11-10-72 WHITTIER, L.C.R.C.  
FOUND 3/4" PIPE IN MON BOX  
WIT.-N30°E, 72.64' - NAIL & TAG IN POWER POLE  
SOUTH, 16.14' - ROAD SIGN  
N25°W, 36.9' - STOP SIGN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4"x15" PIPE IN MON. BOX IN MIDDLE OF ROAD INTERSECTION. OLD WITNESSES HAD BEEN REPLACED BUT WERE IN NEAR PROXIMITY TO ORIGINAL POSITIONS.

Corner, G-7 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433" IN MON. BOX. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
N30°E, 73.80' - NAIL & TAG IN POWER POLE  
SOUTH 16.70' - ROAD SIGN  
N25°W, 41.60' - STOP SIGN  
N40°E, 55.80' - NAIL & TAG IN 4"x4" WOOD POST



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 10-4-96