

ADJUTANT GENERAL'S OFFICE
 P.A. 345 OF 1990
 MIDLAND COUNTY

9/12/96

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

290

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 16N R 1E	H-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 MIDLAND COUNTY
 REMONUMENTATION & FILED

27 NOV 96 2:55 P.M.

BEVERLY J THAYER
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4		3		2		1	
3													
4	7	8				9		10		11		12	
5													
6	18	17				16		15		14		13	
7													
8	19	20				21		22		23		24	
9													
10	30	29				28		27		26		25	
11													
12	31	32				33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1832 PARKE
 SET 1/4 SEC. POST
 WIT.-LYNN 24" N2°W 13 LKS.
 HEMLOCK 11" S12°W 19 LKS.

5-03-04 GIBBS, C.S.R.
 SET PIECE OF WAGON TIRE AT
 AVERAGE DIST ON TRUE LINE

NO DATE GIBBS, C.S.R.
 PIECE OF WAGON TIRE SET IN
 SURVEYS OF SEC. 15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8"x18" RE-ROD. EXCAVATED TO 30" AND FOUND NOTHING ELSE. MEAS EAST 2644.44' (GIBBS 2645.28' & 2644.95') TO G-5. FENCE TO NORTH, 1' WEST OF CORNER.
 TO J-5. MEAS WEST, 2648.44' (GIBBS 2645.28' & 2644.95') TO G-5. SEARCHED DILIGENTLY BUT COULD NOT FIND PIECE OF WAGON TIRE.

Corner, H-5 was approved for remonumentation at a Peer Review Committee Meeting on SEP. 12, 19 96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. P.S. 9433".
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF ACCEPTED POSITION OF THE CORNER.

WITNESSES:
 S53°W, 35.79' - WEST END OF 14" C.M.P.
 S34°E, 30.21' - EAST END OF 14" C.M.P.
 N64°W, 91.66' - NAIL & TAG IN POWER POLE
 N83°E, 148.26' - NAIL & TAG IN POWER POLE



Signed by Paul B. Lapham
 Surveyor's Michigan License No. 9433

Date 10-09-96