

SURVEY & REMONUMENTATION

JAN 21 1999

APPROVED LAND CONSENT
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

372

For corners in 9/09/98

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R01E	I-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on September, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- I-3: 1830 Parke Set Cor to 2, 3, 10 & 11
 - Wit-1) Pine 22" S63W 8 lks
 - 2) Birch 8" N54E 27 lks
- 1907 Gibbs CSR
Old Cor Post Standing
Meas 40.00 East & South
- 1911 Gibbs CSR
Old Cor Post well preserved
Meas 40.00 North
- 4-6-94 Ledy (132) 5-514 Fd 5/8" Rod
Wit-1) SW 44.0 Stop Sign Post
2) NW 48.6 PK In Cor Fence
3) NE 63.2 Center MBT Post
4) E 10.4 Edge Pvm't

- 8-21-98 Robison Unrec Survey Fd 5/8" Rod
Wit-1) N45E 71.60 nail in P.P.
2) N70E 58.70 Stop Sign
3) N45W 48.65 Cor Fence
4) S70W 43.90 Stop Sign
Meas South 2633.26

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3: Found 5/8" x 18" rod in 3/4" x 12" pipe in Monument Box. Found no other evidence. Found 1994 and 1998 witnesses. Measured East 2622.38 to 1/4 Corner. Measured South 2633.17 to 1/4 Corner.
Corner, I-3, was approved for remonumentation at a Peer Review Committee Meeting on 9/09/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S.27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

- Witnesses:
- N45E 71.60', nail & tag, P.P. (OBT)
 - N45W 48.65', nail & tag, Corner Fence Post (OBT)
 - S66E 136.50', nail & tag, 15" Spruce
 - S16E 102.14', nail & tag, 15" Spruce



signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-09-98