

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

9/12/96 *[Signature]*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

286

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 16N R 1E	1-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

27 NOV 96 2:54 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on OCTOBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1832 PARKE SET POST WIT.-BIRCH 22" S59°W 10 LKS. BEECH 12" N57°E 13 LKS.
  - 5-16-07 GIBBS, C.S.R. IRON AND STONE OLD CORNER
  - 7-06-93 LEDY, (132) 5-134 FOUND 3/4" PIPE MEAS. NORTH 5266.34' TO CORNER
  - NO DATE GIBBS, C.S.R. POST WITH IRON AT SIDE OLD CORNER
  - 5-03-04 GIBBS, C.S.R. POST WITH IRON AT SIDE OLD CORNER
  - 5-02-06 GIBBS, C.S.R. POST WITH IRON AT SIDE OLD CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"x24" PIPE WITH PIECES OF ROTTED WOOD AROUND IN CENTER-LINE OF N-S ROAD AND 1' NORTH OF CENTER-LNE E-W ROAD. MEAS. NORTH 2633.62' (GIBBS 2630.76') TO I-4. MEAS. WEST 2644.94' (GIBBS 2645.28' & 2644.95') TO H-5.

Corner, 1-5 was approved for remonumentation at a Peer Review Committee Meeting on SEP 12, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH BRASS CAP STAMPED "MIDLAND CO. REMON. COR. PS 9433" IN MON. BOX. ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE ACCEPTED POSITION OF THE CORNER.

WITNESSES:  
N39°E, 60.26' - N&T IN 19" W. PINE  
N32°W, 95.37' - CENTER OF 4" MAPLE  
S55°W, 51.02' - NAIL & TAG IN POWER POLE  
S10°E, 161.17' - NAIL & TAG IN POWER POLE



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 10-4-96