

APPROVED LAND CORNER

P.A. 345 OF 1990

MIDLAND COUNTY LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

438

11/12/99 JLR

For Corners in Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 16N R. 1W D-3
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN MIDLAND COUNTY RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

Table with 13 rows and 13 columns labeled A-M. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt 40.16, 1/4 Sec Post Hemlock 8 S23E, 19 Y. Birch 10 N16W 4 1981 Wilcox LCRC #551 Fd 1" Iron N01°E, 34.07 Cor. Fe. Post N16°W, 36.02 Fe. Post S06°E, 61.79 8" W. Birch N35°E, 49.99 4" Maple in clump

SURVEY & REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 5/8" x 12" Cabin spike under asphalt pvm't. Excavated but found no other material. Found three 1981 witnesses. Measured West 2645.52 (GLO 2650.56). Measured East 2645.68 (GLO 2651.88). C.S.R. Meas. 2643.96 both ways.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" rod with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in Mon. Box in C.L. Pvm't. Accepted as best available evidence of original position of the corner.

- Witnesses: N35°E, 50.96 N & T in 10" Maple clump of 4 (OBT) N05°W, 57.50 N & T in 5" Maple N21°W, 44.30 N & T in 10" Poplar EN50°W, 74.54 N & T in 8" x 4" x 3" Maple

Signed by Mark R. Robison Surveyor's Michigan License No. 27458



Date 12-1-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975 REVISED JAN., 1983