

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

439

11/12/99

For Corners in
Midland

(County)

Located In:

Corner Code#:

- | | | |
|---|----------------------------|------------|
| 1. Public Land Survey | T. <u>16N</u> R. <u>1W</u> | <u>E-3</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling
in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous
Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt
Cor of 4, 5, 8 & 9
W. Pine 24 N87W 32
W. Pine 11 S8E 21

1917 Gibbs, CSR
Set Pine Root Post
Pine Stmp S83W 27
Pine Stmp N16W 33
Meas. West 40.06

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Measured CSR distance (2643.96) from D-3. Got reaction under new asphalt pvm't about 100 feet West of this point. Could find no other evidence of corner. Set corner on line with D-3 and reaction under pvm't at the same distance measured from C-3 to D-3 per C.S.R. notes. Measured West 2645.68 (GLO 2651.88 & CSR 2643.96). Measured East 2672.96 (GLO 2688.18). Corner falls 2.8 feet South of C.L. Asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in Mon. Box. Accepted as best available evidence of original position of corner.

Witnesses:

N17°E, 55.96 N & T in 5" Maple
N03°E, 102.94 N & T in 8" R. Oak
S32°W, 87.94 N & T in 14" x 6" Ash
S07°E, 69.70 N & T in E. Side 12" x 12" x 12" Maple

SURVEY &
REMONUMENTATION

FEB 25 2000

SECTION

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458



Date 12-1-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983