

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

11/12/99

For Corners in
Midland

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>16N</u> R. <u>1W</u>	<u>F-3</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3						●							
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

SURVEY & REMONUMENTATION

FEB 09 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt
S89-51E 40.73
Set 1/4 Sec Post
Maple 12" S5W 23
Maple 12" N63E 24

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set temporary Point at S.P.M. between E-3 & G-3 off line at GLO deflection. Found good reaction under new pavement 0.5 feet South and 0.32 feet West of S.P.M. position. Accepted good reaction and excavated but could not find anything. Set iron and Mon. Box at this revised position about 2 feet South of C.L. Pvm't. Meas. East 2671.76 (GLO 2687.52). Meas. West 2672.96 (GLO 2688.18).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in Mon. Box. Accepted as best available evidence of original position corner.

Witnesses:
N09°E, 47.88 N & T in 10" x 8" Maple
N04°E, 51.12 N & T in 8" x 2" x 2" Maple
S36°E, 74.74 N & T in 15" x 20" Ash
S02°E, 54.23 N & T in 8" Maple

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458



Date 12-1-99