

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

441

11/12/99 JLR

For Corners in
Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 16N R. 1W G-3
T. _____ R. _____
T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852 Burt
Cor Sec. 3, 4, 9 & 10
Tamarac 8 S19W 39
Tamarac 10 N451/2E 63
1984 Lapham LCRC #596
Set 1/2" x 18" rerod per CSR & GLO Bearings.
- 1902 Gibbs
Subdivided Sec. 4 but did not note measurements to G-3 and did not witness the corner.
S10W 36.1 10" Poplar
S50°E 46.35 5" Poplar
North 4' C.L. Pvm't
N45E 62.7 4" Cherry
North 80.95 West clump of four 8"- 10"Pines

SURVEY &
REMONUMENTATION

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 18" iron under asphalt pvm't. Found four 1984 witnesses. Measured West 2671.76 (GLO 2687.52). Measured East 2660.66 (GLO 2673.0). Corner falls about four feet South of C.L. Pvm't.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S #27458 in Mon. Box. Accepted as best available evidence of original position of corner.

- Witnesses:
- N10°E, 80.94' N & T in 12" x 20" x 12" x 10" Pine (OBT)
 - N33E, 61.86 N & T in 7" x 9" Cherry (OBT)
 - S20°W, 36.10 N & T in 15" Poplar (OBT)
 - S40°E, 46.35 N & T in 9" Poplar

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 12-1-99