

APPROVED LAND CORNER
 P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE
 MIDLAND COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

442

11/12/99 JRP
 For Corners in
Midland
 (County)

	Located In:	Corner Code#:
1. Public Land Survey	T. <u>16N</u> R. <u>1W</u>	<u>H-3</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 MIDLAND COUNTY
 RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt
 40.50 1/4 Sec. Post
 W. Pine 20" S34W, 49
 W. Pine 18" N73E 38

 1902 Gibbs, CSR
 1/4 Corner in Culvert
 Meas. West 20.08 to 1/8 Cor.

1984 Lapham, (132) 3-705 & LCRC #597
 S1/4 Cor. Set 1/2" x 18" Rerod in C.L.
 Road, S.P.M.
 S20°E, 45.6 Pow. Pole
 N40°E, 86.9 30" Oak
 S20°W, 29.65 End of 36" CMP
 West 49.64 Iron in C.L. Road

SURVEY &
 RE-MONUMENTATION

FEB 25 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 18" rerod under asphalt pvm't. Found four 1984 witnesses. Measured East 2647.63 (GLO 2659.8). Meas. West 2660.66 (GLO 2673.0). Got good reaction under pvm't 49.64 West of corner per 1984 LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in Mon. Box. Accepted as best available evidence of original position of corner.

Witnesses:
 S28°W, 31.36 Top Cen.S. End 48" CMP (OBT)
 S15°E, 45.54 N & T in P.P. (OBT)
 N42°E, 86.58 N & T in 30" x 24" W. Oak (OBT)
 N05°W, 99.00 N & T in 14" R. Oak

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 12-1-99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 23, 1971