

# SURVEY & REMONUMENTATION

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

APR 28 1995

COMMISSION

*12/05/94 JBL*

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MIDLAND  
(County)

Located In:

Corner Code #

- |                                       |                          |     |  |
|---------------------------------------|--------------------------|-----|--|
| 1. Public Land Survey                 | T <u>16N</u> R <u>1W</u> | I-7 |  |
|                                       | T _____ R _____          |     |  |
|                                       | T _____ R _____          |     |  |
|                                       | T _____ R _____          |     |  |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  |     |  |
|                                       | S _____ T _____ R _____  |     |  |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  |     |  |
|                                       | S _____ T _____ R _____  |     |  |

**189**

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

21 DEC 94 11:18 A.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

AUSTIN BURT  
WIT.-(1)HEMLOCK 12" S73°E 22 LKS.  
(2)HEMLOCK 18" N53°W 32 LKS.

NO C.S.R.

4-12-89 JONES, (132) SURVEY  
WIT.-(3)MONUMENT 463.6" EAST OF SEC. COR.

3-16-90 ROBISON, (SURVEY)  
FOUND 1/2" IRON IN CONC.  
WIT.-(8)N30°E 71.65' POWER POLE  
(9)EAST 32.61' CONC. MON.  
(10)S45°W 74.80' POWER POLE  
(11)S55°W 62.08' POWER POLE

9-16-92 JONES, (132) SURVEY  
NO WITNESSES

5-4-92 LAPHAM L.C.R.C. #719  
FOUND 3/4" PIPE CAPPED  
WIT.-(4)S25°W 33.35' TELE. RISER  
(5)S35°E 48.00' CENTER 6" ELM  
(6)N20°W 43.35' STOP SIGN  
(7)N45°E 62.20' BURIED CABLE WARNING SIGN  
PBL NOTE: LCRC #719 APPEARS TO BE FILLED IN ERROR.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 18" CONC. MON. WITH 1/2" ROD IN IT WITH A 1/2"x18" RE-ROD UNDER IT. EXCAVATED TO 3' DEPTH. DID NOT FIND FURTHER EVIDENCE.  
FOUND WITNESSES 3, 9 & 11

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, I-7 was approved for remonumentation at a Peer Review Committee Meeting on 12-05, 19 94.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-7: Corner common to Sections 14, 15, 22 & 23  
Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box.

WITNESSES:  
S45°W 62.20' POWER POLE (11)  
N45°W 47.10' COR. FENCE POST  
S30°E 77.7' 16" W. PINE  
EAST 32.61' MONUMENT (9)



Signed by Paul B. Lapham Date 12-19-94  
Surveyor's Michigan License No. 9433