

APPROVED LAND CORNER

444

P.A. 345 OF 1990

MIDLAND COUNTY LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

11/12/99 [Signature]

For Corners in

Midland

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 16N R. 1W J-3
- T. _____ R. _____
- T. _____ R. _____
- 2. Public Controlling S. _____ T. _____ R. _____
- in Section S. _____ T. _____ R. _____
- 3. Miscellaneous S. _____ T. _____ R. _____
- Property in Section S. _____ T. _____ R. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
MIDLAND COUNTY
RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on October 25, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 Burt
39.70 1/4 Sec. Post
Hemlock 12 South 7
Elm 12" N55E 7

1974 Lapham LCRC #331
Fd. P.K. Nail
N45E 59.05 T.P.
N45W 70.74 P.P.
S55W 53.36 P.P.

1992 Jones, (132) 4-950
References corner in survey.
N45W 70.81 P.P.
N45E 57.32 W'y rebar on pro. marker
S50W 63.26 P.P.
S45E 54.23 T.P. Stub

1998 Claypool LCRC #825
Fd P.K. nail
Same witnesses as LCRC #835

1989 Prevost LCRC #662 & (132) 4-527
P.K. nail reset re: recording
N45 - 70.74 fee P. Pole
S50 - 62.85 New Pole
S45E 54.00 Fee T. Pole Stub
N45E 57.47 Ctr. Project Marker

1997 Ciosek, (132) 5-634
Fd P.K. nail & reference LCRC #662
1998 Claypool LCRC #835
Replaced P.K. nail with 9 mm pipe in Mon. Box
NW 21.545m P.P.
NE 17.460m rod on top of pro. marker
SE 16.510m nail in post
SW 19.268m P.P.

SURVEY &
RECONSTRUCTION

FEB 25 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 18" pipe in Mon. Box. Found two 1974 witnesses, three 1989 witnesses, four 1992 witnesses, & three 1998 witnesses. Meas. West 2676.65 (GLO 2677.62). Meas. East 2605.94 (GLO 2620.2). Cor. falls at int. C.L. of roads.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped Midland Co. Remon Corner P.S. #27458 in Mon. Box. Accepted as best available evidence of corner.

Witnesses:

- N45°W, 70.72 N & T in P.P. (OBT)
- S55°W, 63.38 N & T in P.P. (OBT)
- S45°E, 54.12 N & T in P.P. Stub. (OBT)
- N45°E, 57.42 Top. Cen. Project Marker (OBT)

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458



Date 12-1-99

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971