

ADJUTANT GENERAL'S OFFICE
 P.A. 345 OF 1990
 MIDLAND COUNTY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Midland County Remonumentation

431

9/17/99 JRG

For Corners in
Midland

(County)

Located In:

Corner Code#:

- | | | |
|---------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T. <u>16</u> R. <u>1W</u> | <u>K-12</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
 MIDLAND COUNTY
 RECORDED

12/7/1999 2:59:31 PM

SCOTT I. HAINES
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on 6-28-1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|---|---|
| 1852 Burt
1/4 Cor. Set Post
Hemlock 6 S67W 23
Hemlock 8 N61E 30 | 1978 Whittier, (132) 2-753 40.20 Old
References E1/4 Cor
No Witnesses | |
| 1911 Gibbs, C.S.R.
Post Set in Survey of Hwy
Meas. North 40.00
Meas. South 40.06 | 1984 Owens Ayres, (132) 3-588
Mon. In Mon. Box
No Witnesses | 1991 Jones, (132) 4-764
3/8" rod in Mon. Box
N40E 78.36 Nail in P.P.
S87W 29.90 Nail in P.P.
S50E 66.30 Nail in 16" Pine
East 4.5 C.L. Water Rd. |
| 1975 Schafer, (132), 1-837
Fd Mon. in Mon. Box
Mon. 33 West
Meas. North 2638.04 | 1986 Jones, (132) 3-867
References E1/4 Cors.
No Witnesses | |
| 1975 Schafer, LCRC, 354
Same as (132) 1-837 | | |

**SURVEY &
 REMONUMENTATION**

FEB 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Fd 3/8" re-rod in concrete base in Mon. Box. Fd all 1991 witnesses. Meas. North 2637.84 (Rec 2637.92) to K-11. Could not remove re-rod but was able to drive 3/4" x 9" Gas Pipe over re-rod & into old concrete.

Corner K-12, T16N, R1W was approved for remonumentation at a Peer Review Committee Meeting on 9/17/99


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 9" Gas Pipe with Brass Cap stamped "Midland County Remon, Cor. P.S. 27458" over 3/8" re-rod set in concrete base in Mon. Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

- N32°E 78.83', Fd spike in P.P. (OBT)
- S59°E 66.76', Set spike over old spike in W. Side 18" Pine (OBT)
- S11°W 148.04', Set spike in P.P.
- N27°W 58.82', Set spike in 16" Oak

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 11-22-99

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983