

**SURVEY &
REMONUMENTATION**

**APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

193

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>1W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

21 DEC 94 11:19 A.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	1					
5											
6	18	17	16	15	14	1					
7											
8	19	20	21	22	23	2					
9											
10	30	29	28	27	26	2					
11											
12	31	32	33	34	35	3					
13											

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852 AUSTIN BURT
WIT.-ELM 8" S38°W 5 1/2 LKS.
B. ASH 7" N16°W 9 LKS.

6-22-74 JOHN RADCLIFFE L.C.R.C.
MON. BOX IN Q MERIDIAN ROAD.
WIT.-(1)TELE. POLE N45°W 56.77'
(2)POWER POLE S65°W 92.77'
(3)NORTH POST OF ARROW SIGN S88°E 22.93'

1909 GIBBS
SET LONG BOLT WITH SQUARE HEAD ON
TOP 9.89' SOUTH OF CORNER, SECT. 21-28 HUB.
(G.L.O. PLAT MAP OF T16N, R1E SHOWS 6.89)

2-8-88 LEDY, (132) SURVEY
FOUND MON. BOX
NO WITNESSES

1960 MDOT PLAN
3/4" PIPE IN MON. BOX 450.58'(6.83 CH)
SOUTH OF Q BAKER ROAD (21.28 SEC. COR.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8"x36" ROD AND UNDER THAT WAS 3/4"x28" PIPE IN MON. BOX. EXCAVATED TO 3' DEPTH. DID NOT FIND FURTHER EVIDENCE. FOUND WITNESSES #1, 2 & 3.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, M-7 was approved for remonumentation at a Peer Review Committee Meeting on 12-05, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7: SE Corner common to Section 13
Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Monument Box.

WITNESS:
N45°W 56.77' TELE. POLE (1)
S65°W 92.77' POWER POLE (2)
S88°E 22.93' NORTH POST OF ARROW SIGN (3)
Q M-30 1.40' WEST



Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-19-94