

APR 28 1995

111

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 16N R 2E	A-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

11 OCT 94 4:08 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on JUNE, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7: SW Corner, Sec. 18 - NW Corner, Sec. 19
1831 - Harvey Parke, Int. West Boundary 40 lks N, Hemlock 20" S 77°E, 10 lks,
Maple 12" N 11°E, 19 lks

No C.S.R.

01-25-74 - Notes of survey by Leonard Urbaniak from private records of Paul B. Lapham and copy of recorded survey (132) 1-531

8/23/75 - Edmands Eng. R.R. Spike (132) 1-906

1. WEST, 156.9' - Hope Twp. Sign
2. NW, 82.05' - Nail, 12" Elm
3. NE, 46.88' - Nail, 8" Ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7: SW Corner, Sec. 18 - NW Corner, Sec. 19
Established Corner position from S 1/4 Corner & SE Corner, Section 18, from notes of Leonard Urbaniak survey (132) 1-531. Found R.R. Spike laying horizontal under asphalt and gravel.
Found Recorded Witnesses #2 & 3.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner A-7 was approved for remonumentation at a Peer Review Committee Meeting on 9-27, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7: SW Corner, Sec. 18 - NW Corner, Sec. 19
Set 5/8" x 18" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Mon. Box.
N 40°W, 82.92' - Nail & Tag, 12" Elm (2)
N 42°E, 46.78' - Nail & Tag, 8" Ash (3)
S 18°E, 44.42' - Nail & Tag, 8" Elm
N 10°W, 49.39' - Nail & Tag, 8" Elm



Signed by Paul B. Lapham

Date 9-30-94

Surveyor's Michigan License No. 9433