

**SURVEY &  
REMONUMENTATION**

JAN 21 1999

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY**

REMON. COR. B-9, MILLS TWP. SECTION **412**  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

For corners in  
Midland  
(County)

|                                       | Located in:              | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey                 | T <u>16N</u> R <u>2E</u> | <u>B-9</u>    |
|                                       | T ___ R ___              | _____         |
|                                       | T ___ R ___              | _____         |
|                                       | T ___ R ___              | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___        | _____         |
|                                       | S ___ T ___ R ___        | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___        | _____         |
|                                       | S ___ T ___ R ___        | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RODNEY CLAYPOOL, in a field survey on APRIL 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-9 Corner common to Sections 19 and 30

Glo survey, 1830's, set post  
Survey by F. Gibbs, between 1908 and 1913, set 3/4" bar 3' long  
Survey by D. Whittier, 1971, set  
Survey by J. Schafer, 1973, 1977, found 3/4" bar  
Survey by J. Jones, 1982, 1991, 1992, 1995, found 3/4" pipe  
LCRC by J. Schafer, 1973, found 3/4" iron

**WITNESS NOTE:** Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-9 Corner common to Sections 19 and 30

Found 3/4" pipe per surveys by D. Whittier, J. Schafer, J. Jones, and LCRC by J. Schafer

Corner B-9 was approved for remonumentation at a Peer Review Committee Meeting on August 17, 1998.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-9 Corner common to Sections 19 and 30

Found 3/4" pipe per surveys by D. Whittier, J. Schafer, J. Jones, and LCRC by J. Schafer, replaced pipe with 3/4" pipe and brass cap stamped Midland Co. Remon Cor. PS 29241 and mon box, and is accepted as the best available evidence of the position of the accepted corner.

S 30 Deg E, 69.07', nail and disc in power pole (Rec.)  
N 30 Deg W, 62.41', nail and tag in 18" Maple  
N 30 Deg E, 72.64', nail and plastic disc in 4" pipe  
S 30 Deg W, 81.83', nail and plastic disc in 4" tree  
North, 1.0', north edge pavement

Signed by Rodney D. Claypool Date 09-11-98

Surveyor's Michigan License No. 29241

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971  
Revised May 14, 1971  
Revised Jan., 1983

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

