

JAN 21 1999

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

SECTION 411

REMON. COR. C-9, MILLS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/16/1998 12:11:56 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Midland  
(County)

Located in:	T <u>16N</u> R <u>2E</u>	Corner Code #	<u>C-9</u>
	T ___ R ___		_____
	T ___ R ___		_____
	T ___ R ___		_____
	S ___ T ___ R ___		_____
	S ___ T ___ R ___		_____
	S ___ T ___ R ___		_____
	S ___ T ___ R ___		_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, RODNEY CLAYPOOL, in a field survey on APRIL 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-9 Corner common to Sections 19, 20, 29, and 30

- Glo survey, 1830's, post
- Survey by F. Gibbs, 1906, post
- Survey by D. Whittier, 1965 found 3/4" iron, 1971, raised with 1/2" pipe
- Survey by J. Schafer, 1972, 1973, 1977, 1981, found 1/2" pipe and mon box
- Survey by L. Urbaniak, 1973, found re-rod
- Survey by P. Lapham, 1981, found 3/8" re-rod
- Survey by J. Jones, 1983, 1989, 1992, 1995, found 1/2" pipe
- Survey by M. MacDonald, 1984
- Survey by D. Ledy, 1991, 1992, 1993, found 3/4" pipe
- LCRC by J. Schafer, 1972



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Corner common to Sections 19, 20, 29, and 30

Found 1/2" pipe in mon box per surveys by F. Gibbs, D. Whittier, J. Schafer, L. Urbaniak, P. Lapham, J. Jones, M. MacDonald and D. Ledy and LCRC by J. Schafer

Corner C-9 was approved for remonumentation at a Peer Review Committee Meeting on August 17, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Corner common to Sections 19, 20, 29, and 30

Found 1/2" pipe in mon box per survey by F. Gibbs, D. Whittier, J. Schafer, L. Urbaniak, P. Lapham, J. Jones, M. MacDonald, D. Ledy and LCRC by J. Schafer, replaced pipe with 5/8" rod and brass cap stamped Midland Co. Remon Cor. PS 29241, and is accepted as the best available evidence of the position of the accepted corner.

- S 45 Deg E, 78.91', nail and disc in power pole (Rec.)
- S 40 Deg W, 55.60', nail in telephone pole stub (Rec.)
- N 50 Deg W, 38.43', nail in power pole
- N 45 Deg E, 49.20', notch in W end 18" CMP

Signed by Rodney D. Claypool

Date 09-11-98

Surveyor's Michigan License No. 29241