

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

REMON. COR. F-1, MILLS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

301

For corners in  
Midland  
(County)

Located in: Corner Code #

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>16N</u> R <u>2E</u> | <u>F-1</u> |
|                                       | T ___ R ___              | _____      |
|                                       | T ___ R ___              | _____      |
|                                       | T ___ R ___              | _____      |
| 2. Property Controlling in Section    | S ___ T ___ R ___        | _____      |
|                                       | S ___ T ___ R ___        | _____      |
| 3. Miscellaneous Property in Sec.     | S ___ T ___ R ___        | _____      |
|                                       | S ___ T ___ R ___        | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

13 DEC 96 2:06 P.M.

BEVERLY J THAYER  
Register of Deeds Stamp & File Number  
REGISTER OF DEEDS

I, RODNEY CLAYPOOL, in a field survey on DEC. 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-1 North 1/4 corner Section 4  
Not set by Government survey



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 North 1/4 corner Section 4  
Set 3/4" pipe and brass cap in mon box at average distance between (E-1 and G-1) on controlling Bentley Township Townline, Gladwin Co.

Corner F-1 was approved for remonumentation at a Peer Review Committee Meeting on Nov 12, 96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 North 1/4 corner Section 4  
Set 3/4" pipe and brass cap in mon box stamped Midland Co. Remon Cor. PS 29241 at average distance between (E-1 and G-1) on controlling Gladwin Co. Townline; and is accepted as the best available evidence of the position of the accepted corner.

- West 25.76', 3/4" pipe (F-13 Bentley Township, Gladwin County)
- N 40 Deg E, 28.31', pk nail and plastic disc in 8" Ash
- S 10 Deg, 10.23', pk nail and plastic disc in 8" Ash
- S 85 Deg W, 53.77', nail and plastic disc in 24" Maple
- S 15 Deg W, 45.13', pk nail and plastic disc in 24" Maple clump
- S 60 Deg E, 36.88', nail and plastic disc in 10" Oak

Signed by Rodney D. Claypool Date 12-12-96

Surveyor's Michigan License No. 29241