

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

11/12/96

REMON. COR. G-2, MILLS TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

302

For corners in  
Midland  
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>2E</u>	<u>G-2</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

13 DEC 96 2:06 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, RODNEY CLAYPOOL, in a field survey on MARCH 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-2 1/4 corner common to Sections 3 and 4  
Wood post Government survey, 1830

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 1/4 corner common to Sections 3 and 4  
Nothing found (could have been removed during road construction)  
Set brass cap on 5/8" re-rod in mon box at prorated distance on straight line between G-1 and G-3.

Corner G-2 was approved for remonumentation at a Peer Review Committee Meeting on 11/12/96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 1/4 corner common to Sections 3 and 4  
Set brass cap on 5/8" re-rod in mon box at prorated distance on straight line between G-1 and G-3; and is accepted as the best available evidence of the position of the accepted corner.  
S 40 Deg E, 57.32', nail in power pole  
N 75 Deg E, 54.18', nail and plastic disc in 6" Oak  
N 85 Deg W, 29.24', nail and plastic disc in 4" x 4" telephone post  
S 75 Deg W, 57.05', nail and plastic disc in power pole  
East 3.0', centerline bit. road

Signed by Rodney D. Claypool Date 12-11-96

Surveyor's Michigan License No. 29241