

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

SURVEY &
REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

104

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T 16N R 2E	J-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

11 OCT 94 4:06 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PAUL B. LAPHAM, in a field survey on MAY, 19 94, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- J-11: 1/4 Corner common to Sections 26 and 35
1831 - Harvey Parke Beech 12" S 17°E 11 lks, Hemlock 12" N 64°W 11 lks
No C.S.R.
9-22-77 - Paul Lapham (132) 2-514
1. N 05°W, 37.25' - Corner Post
2. S 05°W, 33.60' - Corner Post
3. S 10°E, 37.29' - 12" Oak
4. S 40°E, 50.43' - 18" Poplar
11-10-77 - Paul Lapham L.C.R.C. #438
Notes indicate he set 1/2" Capped Re-rod single proportionate measure between SW & SE Section Corners.
4 Witnesses - as above

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11: 1/4 Corner common to Sections 26 and 35
Found 3/4" X 18" pipe in Mon. Box. Excavated to 3 feet, found no other evidence.
Measured East, 2642.87 feet (Previous Survey 2642.72) to K-11.
Measured West, 2642.86 to I-11.
Found Witnesses # 2, 3 & 4 above.

Accepted as best available evidence of the reestablishment of the position of the original corner & replaced with Standard Monument.

Corner J-11 was approved for remonumentation at a Peer Review Committee Meeting on 9-27, 1994.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11: 1/4 Corner common to Sections 26 and 35
Set 3/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Mon. Box.
N 24°W, 85.5' - 15" Oak - Nail & Tag
NORTH, 51.75' - Power Pole - Nail & Tag
S 32°W, 41.04' - 10" W. Pine - Nail & Tag
S 10°E, 37.29' - 18" Oak (3) - Nail & Tag



signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 9-30-94