

REMONUMENTATION

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

105

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

*3/22/94 JBJ*

corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>16NR</u> <u>2E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
In Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

11 OCT 94 4:07 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PAUL B. LAPHAM, in a field survey on MAY, 19 94,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- K-11: Corner common to Sections 25, 26, 35 and 36  
1831 - Harvey Parke, Poplar 8" S 49°E 19 lks, Pine 8" N 27°W 33 lks  
No C.S.R.
- 7-17-71 - Alva Courtwright, Mon. Box set over R.R. spike over old corner when road was blacktopped. L.C.R.C.#106  
1. NE ? TP, 2. SE 48.5' R/W Marker, 3. SW 70.45' PP
- 6-19-72 - Arthur Leach, R.R. Spike in Mon. Box (132) 1-160  
1. N 45°E 45.4' Nail, SE face PP, 2. S 45°E 48.6' C conc. R/W Marker, 3. S 45°W 70.5' Nail in PP
- 9-22-77 - Paul Lapham, Found Iron in Mon. Box (132) 2-514  
1. N 45°E 45.4' PP, 4. N 45°W 49.55' Fence Post, 2. S 40°E 48.55' R/W Marker, 5. S 45°W 68.13' PP
- 5-15-78 - Edmonds Eng. Found R.R. Spike in Mon. Box (132) 2-614.  
1. NE 44.95 Face of PP, 2. SE 48.2' W. Cor. Conc. Proj. Marker, 5. SW 68.13' Spike in PP
- 12-87 - Ledy Eng. Found Spike in Mon. Box (132) 4-177 (also 4-176 & 4-582)  
6. N 70°W 127.80' 60p Spike, 14" Twin Oak, 1. N 45°E 45.40' 60p Spike, c/o PP, 5. S 45°W 68.26' 60p Spike, PP

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-11: Corner common to Sections 25, 26, 35 and 36  
Found R.R. Spike over 1" x 14" Pipe. Excavated to 3' depth, did not find further evidence.  
Found Witnesses #1, 5 & 6.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner K-11 was approved for remonumentation at a Peer Review Committee Meeting on 9-27, 19 94.  
Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-11: Corner common to Sections 25, 26, 35 and 36  
Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433" in Mon. Box.  
N 45°E, 46.2' - Spike in Cut-off Power Pole (1)  
S 45°W, 68.26' - Spike in Power Pole (5)  
N 70°W, 127.8' - Spike in Twin 14" Oak (6)  
S 38°E, 100.6' - Spike in 6" Maple

Recorded by Paul B. Lapham

Date 9-28-94

Surveyor's Michigan License No. 9433