

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

11/2/96 JFR

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16</u> N R <u>2</u> W	<u>E-1</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

20 DEC 96 2:05 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MARK R. ROBISON, in a field survey on OCTOBER, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1832 WRIGHT
WIT.-INT. NORTH BDY. 1 CH. 34 LKS.
EAST OF POST. SET POST.
B. ASH 14" S25°E 26 LKS.
ELM 18" S60°W 50 LKS.

11-13-01 GIBBS, C.S.R.
WIT.-OLD CORNER POST STANDING.

10-14-10 GIBBS, C.S.R.
WIT.-OLD CORNER POST STANDING.

8-14-72 WHITTIER, L.C.R.C.
WIT.-FOUND 4" OAK POST SET BY HASTINGS ABOUT 1900.
DROVE 3/4" PIPE IN CENTER.
WEST 88.65' - TOWN CORNER TO NORTH.
N50°W, 68.80' - N&T IN UTILITY POLE.
S70°E, 51.80' - N&T IN N. SIDE TWIN 14" MAPLE.
N80°W, 36.85' - N. END 48" C.M.P.

9-6-72 WHITTIER, (132) L.1, PG. 203
WIT.-SAME AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4"x18" PIPE. FOUND ALL FOUR 1972 WITNESSES. STANDARD CORNER IS GLADWIN COUNTY MONUMENT.

Corner, E-1 was approved for remonumentation at a Peer Review Committee Meeting on 11-12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4"x18" GAS PIPE WITH STANDARD MON. CAP AT CORNER.
ACCEPTED CORNER AS BEST AVAILABLE EVIDENCE OF PERPETUATION OF ORIGINAL CORNER.

WITNESSES:
WEST, 88.65' - CORNER FOR TWP. TO NORTH (OBT). (E-13 T17N-R2W)
N50°W, 68.80' - NAIL & TAG IN POWER POLE (OBT).
S70°E, 51.80' - NAIL & TAG IN TWIN 16" MAPLE (OBT).
S32°E, 79.42' - NAIL & TAG IN 15" OAK.
N55°W, 125.92' - NAIL & TAG IN 21" MAPLE.



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-19-96