

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

8/28/97

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MIDLAND</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>2W</u>	<u>G-2</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

344

STATE OF MICHIGAN
MIDLAND COUNTY
FILED
REMONUMENTATION
11 DEC 97 12:00 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright
Wit-Maple 18 S39W 29 lks
Hemlock 9 N39E 21 lks

8-21-17 Gibbs, C.S.R.
Set new post in place of
old corner set in 1901
Meas North 41.16 to G-1
Meas South 40.13 to G-3

9-12-83 Lapham (132) 3-868
Fd 1/2" bar bent. Set 1/2" C.I.
Wit-East 34.88 Cor. Fence Post
S50E 37.10 4" Spruce
N50W 55.20 14" Pine

11-13-01 Gibbs, C.S.R.
Set piece of sleigh shoe
Wit-Pine Stump S35E 62
Meas North 41.17 to G-1
Meas South 40.09 to G-3

7-19-74 Lapham, L.C.R.C. 312
Set 1/2" bar (Set on fence line & C/L road)
Wit-East 34.60 Cor Fence Post
S88W 29.75 Cor Fence Post
N50W 55.29 10" Pine Tree

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron; removed & searched for sleigh shoe, could not find. Found Fence Corner East 34.88', in poor condition. Found 16" Pine N45W, 55.20'. Distance South to G-3 is 2646.50' and North 2715.78' to G-1.

SURVEY &
REMONUMENTATION

FEB 24 1998

Corner, G-2 was approved for remonumentation at a Peer Review Committee Meeting on August 28, 1997.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:
N45W, 55.20', nail & tag, 16" Pine (OBT)
S75E, 32.20', nail & tag, 15" Pine
West, 47.38', nail & tag, Utility Pole Fence Post
S35E, 57.38', nail & tag, 10" Pine

Signed by *Mark R. Robison*
Surveyor's Michigan License No. 27458

Date 10-31-97

