

JAN 21 1999

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND County Remonumentation SECTION

414

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2/09/98 2/19

For corners in

_____ MIDLAND _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R02W	G-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MIDLAND COUNTY
REMONUMENTATION & FILED

12/30/1998 1:33:41 PM

BEVERLY J. THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Mark R Robison, in a field survey on July, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-4: 1830 Wright 1/4 Sec Post
Wit-Elm 18" S68E 35 lks
Maple 10" N62W 31 lks

1901 Gibbs CSR
Set new Cedar Post in place of old one.
B.T. found.
Meas North 38.98 and South 40.00

1910 Gibbs CSR
Cedar Post set in survey Sec 9 in 1901
Measured North 40.10 and South 40.10

1-7-77 Lapham LCRC#415
Fd Magnetic reading in Asphalt
Set nail & tag
Wit-West 26.56 8" Post
East 23.06 6" Post
N30W 75.19 4" Pine

10-22-79 Lapham unrecorded survey
Nail & Tag over Iron
Wit-same as LCRC#415

9-24-80 Merry (132) 3-131
Fd 1/2" Iron rod in centerline of road
Wit-none
Meas 2647.91 North

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4: Found 1/2" Iron in center of North-South Road at intersection of fence East-West. Measured South 2648.48 (CSR 2646.6 & 2640.00) to Section Corner. Measured North 2647.88 (CSR 2638.68 & 2646.6, Merry 2647.91). Found 1977 witnesses.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon Cor. P.S.#27458" in Monument Box.
Accepted as best available evidence of the accepted position of the corner.
West 30.10 Nail & Tag in Post
East 23.06 Nail & Tag in Post (OBT)
N30W 75.19 Nail & Tag in 20" Pine (OBT)
S40E 142.84 Nail & Tag 7" Elm

Signed by Mark R Robison
Surveyor's Michigan License No. 27458



Date 12-21-98