

JAN 21 1999

APPROVED FOR CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

MIDLAND County Remonumentation

LAND CORNER RECORDATION CERTIFICATE SECTION  
Filing Requirement of Act 74, Mich. P.A. 1970

415

9/09/98 *[Signature]*

For corners in

MIDLAND  
(County)

Located in:

Corner Code #

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/30/1998 1:33:41 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- |                                    |           |     |
|------------------------------------|-----------|-----|
| 1. Public Land Survey              | T16N R02W | G-5 |
|                                    | T R       |     |
|                                    | T R       |     |
|                                    | T R       |     |
| 2. Property Controlling in Section | S T R     |     |
|                                    | S T R     |     |
| 3. Miscellaneous Property in Sec.  | S T R     |     |
|                                    | S T R     |     |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark R Robison, in a field survey on July, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

G-5: 1830 Wright Sec Cor 9, 10, 15 & 16  
Wit-Beech 8 S57E 20 lks  
Beech 12 N48W 39 lks

1901 Gibbs CSR  
Stone--stone around  
Measured North 40.00 & West 39.94

1903 Gibbs CSR  
Stone--stone around  
Measured South 40.16 & West 40.09

1910 Gibbs CSR  
Post & stone--stone around  
Measured North 40.10 & East 80.15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5: Found 1/2" Iron in centerlines of East-West & North-South road. Measured North 2648.48 (CSR 2646.6 & 2640.0) to G-4. Measured South 5282.48 (CSR 5302.44) to G-7. Measured West 2639 to 1/4 line fence. Measured East 2630.12 to 1/2" Iron on fenceline to South. Center of county drain ditch is 814 feet North (GLO 726 feet).

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon Cor. P.S.#27458" in Monument Box.  
Accepted as best available evidence of the accepted position of the corner.

N47W 71.06' Nail & Tag in P.P.  
N86E 142.84 Nail & Tag in P.P.  
N45E Notch East end 24" CMP, 27.96'  
S45W 30.70 Notch in West end 24" CMP

Signed by *[Signature]*  
Surveyor's Michigan License No. 27458



Date 12-21-98