

JAN 21 1999

APPROVED TO RECORD

P.A. 945 OF 1998  
MIDLAND COUNTY

MIDLAND County Remonumentation

SECTION

9/09/98 JJA

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

416

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R02W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

12/30/1998 1:33:41 PM

BEVERLY J. THAYER  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Mark R Robison, in a field survey on July, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- G-6: 1830 Wright 1/4 Sec Post  
Wit-B. Ash 10 S45W 23  
Elm 18 N33E 25
- 1903 Gibbs CSR-57  
Set Cedar Post at avg dist on true line  
Measured North 40.16  
Measured South 40.18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6: Found no evidence of corner. Set at S.P.M. between section corners. Corner falls in asphalt road 4 feet North of old fence to West, 6 feet North of fence to East and 2 feet East of centerline. Measured 2641.24 North and South to section corners (CSR is 2650.56 North and 2651.88 South; but notes say corner was set at average distance.)

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6: Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon Cor. P.S.#27458" in Monument Box.
- Accepted as best available evidence of the accepted position of the corner.
- S87E 25.48 Nail & Tag Fence Post
- N88W 40.90 Nail & Tag Twin Maple 14" & 10"
- N65W 38.86 Nail & Tag Triple Maple
- N25W 72.04 Nail & Tag Twin Maple

Signed by Mark R. Robison

Surveyor's Michigan License No. 27458



Date 12-21-98