

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

346

8/28/97

For corners in

MIDLAND (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>2W</u>	<u>1-1</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

STATE OF MICHIGAN
MIDLAND COUNTY
FILED &
REMONUMENTATION
11 DEC 97 12:00 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1830 Wright
Int 25 lks East of Post
Wit.-Hemlock 16 S60W 13 lks
Do. 10 S49E 38 lks
 - 8-21-17 Gibbs, C.S.R.
Old Cor Post decayed.
Set new post stone around
Meas South 11.03 & 29.82 to I-2
Meas West 40.24 to H-1
 - 7-19-74 Lapham, L.C.R.C. 312
Fd 1" x 3" old gear
Wit.-S40E 42.83 T.P.
S50W 50.38 Cor. F. Post
N40W 54.98 Cor. F. Post
 - 1916 Gibbs, C.S.R.
Old Cor Fd. From stone & post-.25W-
S. Cor to Sec 34 & 35 Beaverton Twp.
Meas South 20.84 & 19.97 to I-2
Meas East 39.78 to J-1
 - 9-27-29 C.S.R., Note on C.S.R.-125
Round iron at this point with
stone and gear

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" x 3" bar. Found 1/2" iron for Standard Corner I-3, T17N, R2W, 16.4 feet West. Found remains of old fence post at N40W, 54.98 feet (OBT).

SURVEY &
REMONUMENTATION

FEB 24 1998

Corner, I-1 was approved for remonumentation at a Peer Review Committee Meeting on August 28, 1997.

SECTION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as perpetuation of C.S.R.
- Witnesses:
S59W 47.18', nail & tag, Cor. Fence Post
S66E 90.52', nail & tag, 36" Maple
N51W 127.52', nail & tag, 15" Poplar
N38E 92.08' S.W. Cor. Garage
West 16.40' Standard Corner



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97