

APPROVED LAND CORNER
P.A. 345 OF 1990
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

317

8/28/97 JLR

For corners in

| MIDLAND (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>16N</u> R <u>2W</u> | <u>1-2</u> |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

STATE OF MICHIGAN
MIDLAND COUNTY
FILED
REMONUMENTATION
11 DEC 97 12:00 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **MARK R. ROBISON**, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | ● | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright
Wit.-Beech 6 East 2 lks
Do 8 N62W 23 lks

8-21-17 Gibbs, C.S.R.
Iron set in 1916
North 29.82 & 11.03 to I-1
South 39.98 to I-3

7-19-74 Lapham, L.C.R.C. 312
Wit.-same as 4-08-74

1916 Gibbs, C.S.R.
Set Hemlock Post Iron ?
N.B. Found stone S83E 50 1/2
North 19.97 1/3 & 20.84 to I-1
South 39.94 2/3 to I-3

4-08-74 Sedgman (132) 1-638-Set 1/2" bar
Wit.-S89E 28.45 Cor F. Post
S54E 36.93 3" Maple Cluster
S63W 37.35 F. Post
Set from C.S.R. witnesses
(notes refer to 1916 survey)

2-9-89 Ledy (132) 4-357
Found 1/2" bar
Wit.-same as 4-08-74

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar 1 1/2 feet deep, at surface of old gravel road. Old fence corner 32 feet East. Removed iron and searched for 1916 iron & witness; did not find. Found remains of fence post at S89E, 28.45 & Maple Cluster OBT.

SURVEY &
REMONUMENTATION

Corner, I-2 was approved for remonumentation at a Peer Review Committee Meeting on August 28, 1997.

FEB 24 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of perpetuation of C.S.R. corner.

Witnesses:
S49E, 36.93', nail & tag, Maple Cluster (OBT)
S67E, 66.06', nail & tag, 8" Maple
N57E, 95.62', nail & tag, Maple Cluster
S.W. 32.68', nail & tag, 10" Post

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

