

APPROVED LAND CORNER  
P.A. 345 OF 1000  
MIDLAND COUNTY

MIDLAND COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

8/28/97 *[Signature]*

For corners in

MIDLAND  
(County)

Located In:

Corner Code #

- |                                    |       |                   |            |
|------------------------------------|-------|-------------------|------------|
| 1. Public Land Survey              |       | <u>T 16N R 2W</u> | <u>1-3</u> |
|                                    |       | T ___ R ___       | _____      |
|                                    |       | T ___ R ___       | _____      |
|                                    |       | T ___ R ___       | _____      |
| 2. Property Controlling in Section | S ___ | T ___ R ___       | _____      |
|                                    | S ___ | T ___ R ___       | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ | T ___ R ___       | _____      |
|                                    | S ___ | T ___ R ___       | _____      |

348

STATE OF MICHIGAN  
MIDLAND COUNTY  
FILED &  
*REMONUMENTATION*  
11 DEC 97 12:01 P.M.

Register of Deeds Stamp & File Number  
REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright  
Wit.-Hemlock 10 S48E 21 lks  
Maple 12 N35W 21 lks  
1916 Redman, C.S.R.  
Caulter--angle iron & stone  
Wit.-N71 degrees 30 minutes E 80 1/2  
24" Pine Stump  
North 39.94 2/3 to I-2  
East 39.76 1/2 to J-3  
8-21-17 Gibbs, C.S.R.  
Iron, stone around

North 39.98 to I-2  
West 40.24 to H-3  
7-12-72 Courtright, L.C.R.C. 160  
Fd. nail in black top  
Wit.-N45E 63.30 P.P.  
S45E 49.95 P.P.  
N60W 87.80 P.P.  
6-14-73 Sedgman (132) 1-515  
Wit.-same as 7-12-72  
East 2620.16 to J-3  
South 2700.50 to I-4

2-14-74 Lapham, L.C.R.C. 282  
Fd. nail  
Wit.-same as 7-12-72  
4-08-74 Sedgman (132) 1-638  
References L.C.R.C. 282  
North 2640.54 to I-2  
West 2649.36 to H-3  
2-09-89 Ledy (132) 4-357  
Wit.-same as 7-12-72  
Found 1/2" iron rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in asphalt. Excavated and found no other evidence.

SURVEY &  
REMONUMENTATION

FEB 24 1998

Corner, I-3 was approved for remonumentation at a Peer Review Committee Meeting on August 28, 1997.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:  
N42E 63.30', nail & tag, P.P. (OBT)  
S45E 52.70', nail & tag, P.P. (new)  
N48W 87.80', nail & tag, P.P. (OBT)  
S27W 90.78', nail & tag, Triple 40" Maple

Signed by *Mark R. Robison*  
Surveyor's Michigan License No. 27458

Date 10-31-97

